



MINIMUM EXCAVATION SIZE:
7'-6" x 11'-0" x DEPTH REQUIRED.

- (A) 60" BOTTOM SECTION. WT.= 15,400 Lbs.
- (B) TRANSFORMER PAD. WT.= 12,060 Lbs.
- (C) 5" DIA. CAST-IN TERMINATORS
- (D) 30" X 48" ACCESS COVER
- (E) SUMP
- (F) UNISTRUT AS REQUIRED
- (G) TRANSFORMER CABLE ACCESS OPENINGS AVAILABLE IN DIFFERENT SIZES.

■ ASSEMBLY TO BE PLACED ON A 6" BASE OF CRUSHER RUN FOR EASE OF INSTALLATION AND EVEN LOAD DISTRIBUTION.

■ ILLUSTRATION IS TYPICAL ONLY OF GENERAL SERIES CONFIGURATION; FOR SPECIFIC CONFIGURATION, CALL JENSEN PRECAST.

10'-0" x 12'-0"
TRANSFORMER PAD WITH
5'-0" x 8'-6" x 5'-0" DEEP
VAULT

JENSEN
PRECAST®

PD120144

ORG. DWG. DATE
10-24-00

REV. DWG. DATE